

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-025-20-632-0000

LEASE NAME Fox

WELL NUMBER 1-8

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 8 TWP. 34S RGE. 23W (E) or (W)

COUNTY Clark

Date Well Completed 12-3-82

Plugging Commenced 4-1-95

Plugging Completed 4-5-95

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Midco Exploration, Inc.

ADDRESS 414 Plaza Dr., Ste 204, Westmont, IL 60559

PHONE 316 624-0156 OPERATORS LICENSE NO. 5254

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-1-95 (date).

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Chester Depth to Top _____ Bottom _____ T.D. 5480

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|-------------|------|------|-------|--------|------------|
| Chester | gas & water | 5435 | 5442 | 8 5/8 | 762 | 0 |
| | | | | 4 1/2 | 5479 | 4515 |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Pump 200# of hulls @ 20 sks. of cement to 5200'
Pump 50 sks. of cement @ 800'
Pump 40 sks. of cement @ 400'
Put 10 sks. of cement from 40 to 0' Cut off & cap 8 5/8 4' below ground level.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6548

Address P.O. Box 506 Liberal, Kansas 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Midco Exploration Inc.

STATE OF Kansas COUNTY OF Seward, ss.

Keith Hill, agent (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Crown Consulting, Inc.
P. O. Box 1816, Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 28th day of April, 19 95

[Signature]
 Notary Public

My Commission Expires: _____

NOTARY PUBLIC, State of Kansas
 Seward County
 HELEN M. SMITH
 My Appt. Exp. 3-3-97

RECEIVED
 CORPORATION COMMISSION
 MAY 01 1995
 5-01-95
 CONSERVATION DIVISION
 WICHITA, KANSAS