

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-025-20,577-0000

LEASE NAME CUNNINGHAM

WELL NUMBER 1-6

2310 Ft. from S Section Line

1500 Ft. from E Section Line

SEC. 6 TWP. 34S RGE. 23 (E) or (W)

COUNTY Clark

Date Well Completed 1/83

Plugging Commenced 11-24-86

Plugging Completed 11-25-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR MESA OPERATING LIMITED PARTNERSHIP

ADDRESS P.O. BOX 2009, AMARILLO, TEXAS 79189

PHONE#(806) 378-1000 OPERATORS LICENSE NO. 04824

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Richard Lacey - Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Kansas City Depth to Top 4712' Bottom 4723' T.D. 7300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Kansas City	oil	4712	4723	8 5/8"	760'	3'
Marmaton	gas	5088	5092	4 1/2"	5235'	2758'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

CIBP @ 4650' w/20' cement on top; loaded hole w/9.0 ppg mud; cut 4 1/2" @ 2755'; pumped 20 sx cement plug 940'-740'; 40 sx cement plug 800-600'; 10 sx cement plug @ 40'; cut casing 3' BGL; welded on casing cap, well P&A 11-25-86

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pool Company License No. 7874

Address P.O. Box 4271, Houston, Texas 77210

STATE OF Texas COUNTY OF Potter, ss.

Carolyn L. Cummings (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carolyn Cummings
(Address) P.O. Box 2009, Amarillo, TX 79189

SUBSCRIBED AND SWORN TO before me this 1st day of December, 19 86

Stutina Pitts
Notary Public

My Commission Expires 8-5-89

DEC 3

xc: KCC (0+1), Prod Rcds, Reg, CR, Expl, Accts, Land
CONSERVATION DIVISION
Wichita, Kansas

Form CP-
Revised 08-8