


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Clark County. Sec. 34 Twp. 34S Rge. 22W (E) (W)
Location as "NE/CNW%SW%" or footage from lines C SE SE
Lease Owner J. M. Huber Corporation
Lease Name Arnold Well No. 2
Office Address Box 978 Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-4 19 58
Application for plugging filed _____ 19 _____
Application for plugging approved _____ 19 _____
Plugging commenced 9-4 19 58
Plugging completed 9-4 19 58
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives
Producing formation none Depth to top _____ Bottom _____ Total Depth of Well 5730 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|---------|--------|------------|
| | | | | 13-3/8" | 131' | none |
| | | | | 8-5/8" | 2343' | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 470' with mud. Set plug at 470' and cemented thru drill pipe with 35 sacks cement. Filled hole to 35' with mud. Set plug at 35' and cemented to top with 15 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 9 1958
9-9-58
CONSERVATION DIVISION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. M. Huber Corporation
Address Box 978 Liberal, Kansas

STATE OF Kansas COUNTY OF Seward, ss.
W. W. Henson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. W. Henson
W. W. Henson - Prod. Supt.
Box 978 Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this fifth day of September, 1958

Frederick Garcia
Notary Public.

My commission expires 5-1-61

PLUGGING
FILE SEC 34 T 34 R 22W
BOOK PAGE 126 LINE 27

WELL LOG

WELL NAME: Arnold #2

WELL LOCATION: Center of SE/4 of SE/4 of Section 34, Township 34S, Range 22W, Clark County, Kansas

WELL OWNER: J. M. Huber Corporation

DRILLING COMMENCED: 8-14-58

DRILLING COMPLETED: 9-4-58

WELL COMPLETED: 9-4-58

TOTAL DEPTH: 5730'

| <u>FORMATION</u> | <u>DEPTH</u> |
|--------------------------------|--------------|
| Red bed | 0 - 131 |
| Red bed, shells | 131 - 771 |
| Red bed | 771 - 784 |
| Red bed, shells | 784 - 1700 |
| Red bed, lime stringers | 1700 - 1835 |
| Red bed, shale, shells | 1835 - 1838 |
| Red bed, shells | 1838 - 2040 |
| Red bed, shale, lime stringers | 2040 - 2068 |
| Shale, lime | 2068 - 2198 |
| Lime, shale, salt | 2198 - 2220 |
| Lime | 2220 - 2290 |
| Lime, shale | 2290 - 2343 |
| Lime | 2343 - 2357 |
| Lime, shale | 2357 - 2638 |
| Lime | 2638 - 2803 |
| Lime, shale | 2803 - 3289 |
| Lime | 3289 - 3345 |
| Lime, shale | 3345 - 3610 |
| Shale | 3610 - 3822 |
| Lime | 3822 - 3831 |
| Shale | 3831 - 3847 |
| Lime | 3847 - 4030 |
| Lime, shale | 4030 - 4185 |
| Shale | 4185 - 4225 |
| Lime, shale | 4225 - 4547 |
| Lime | 4547 - 4615 |
| Lime, shale | 4615 - 4671 |
| Lime | 4671 - 4817 |
| Lime, shale | 4817 - 4882 |
| Lime | 4882 - 5030 |
| Lime, shale | 5030 - 5200 |
| Lime | 5200 - 5237 |
| Lime, shale | 5237 - 5239 |
| Lime, shale, chert | 5239 - 5293 |
| Lime, shale | 5293 - 5583 |
| Shale, sand | 5583 - 5605 |
| Lime | 5605 - 5662 |
| Lime, shale | 5662 - 5678 |
| Lime | 5678 - 5730 |
| Total Depth | 5730 |

RECEIVED
OPERATION COMMISSION
SEP 9 1958
VISION

STATE OF KANSAS, COUNTY OF SEWARD, ss.

W. W. Henson, employee of owner of the above-described well, being first duly sworn on oath, says: That I have knowledge of facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct.

W. W. Henson
W. W. Henson

Subscribed and sworn to before me this 4th day of September, 1958

Frederick H. Hagg
Notary Public

| | |
|----------|-------------------|
| PLUGGING | |
| FILE | SEC 34 T 34 R 22W |
| BOOK | PAGE 128 LINE 27 |

My commission expires: 5-1-61