

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give all Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Clark County. Sec. 28 Twp. 34 Rge. (E) 22 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines C. NW NW
Lease Owner J. M. Huber Corporation
Lease Name Arnold #1 Well No.
Office Address 916 S. Pine Street - Pratt, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 25, 1952 19.
Application for plugging filed August 25, 1952 19.
Application for plugging approved August 25, 1952 19.
Plugging commenced August 26, 1952 19.
Plugging completed August 26, 1952 19.
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production 19.
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 5692' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				13 3/8"	240'	None
				9 5/8"	2200'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set Halliburton Plug w/1/2 sack of Cotton Seed
Hulls at 300' and spotted 25 sacks of cement.

Set second plug at 35' and spotted 15 sacks of
cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1952
9-16-52
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to J. M. Huber Corporation
Address Drawer 460
Pratt, Kansas

STATE OF KANSAS, COUNTY OF PRATT, SS.
I, J. L. Kyler (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature) *J. L. Kyler*
Box 460 Pratt, Kans
(Address)

SUBSCRIBED AND SWORN to before me this 16 day of September, 1952

Sarah J. Rives
Notary Public.

My commission expires January 26, 1953

PLUGGING
FILE SEC 28 T. 34 R. 22
BOOK PAGE 40 LINE 27

DRILLER'S LOG

COMPANY: VICKERS, REISER & PATTERSON EASTERN
 CONTRACTOR: J. M. RUBER CORPORATION

LOCATION: C HW NW Sec. 28-343-22W,
 Clark County, Kansas

FARM NAME: Arnold No. 1

PRODUCTION: D & A

COMMENCED: 7-16-52

COMPLETED: 8-27-52

ELEVATION: 1327 derrick floor

CASING USED: 13 3/8" at 240' with 200 sacks of cement
 9 5/8" at 2200' with 500 sacks of cement,
 10 sacks of jell, and 125 sacks of
 strata crate

	<u>FROM</u>	<u>TO</u>	<u>TOPS:</u>
Shale	0	500	Hechner 4228
Line and Shale	600	2300	Lansing-K.C. 4418
Chert and Line	2300	2410	Drill stem test 4457-4498, open 40 min., closed 18 min., recovered 2130' salt water, BHSIP 1780 1/2, no shows.
Line	2410	2480	
Sandy Line	2480	2720	
Line and Shale	2720	3025	Karnton 3048
Line	3025	3440	Cherokee 3242
Shale	3440	3785	Morrow 3304
Shale	3785	4110	Drill stem test 5367-5407, open 30 min., recovered 15' mud, 0 BRP
Sandy Shale	4110	4180	
Line	4180	4200	Mississippi 5493
Shale	4300	4420	Drill stem test 5558-5628, open 30 min., weak blow for 15 min. and then died, 165' drilling mud, 0 BRP
Line	4420	5110	Schlumberger total depth 5698
Shale	5110	5140	
Cherty Line	5140	5540	
Line and Shale	5540	5594	
Sand	5594	5596	
Line and Shale	5598	5500	
Line	5500	5698	

DRY AND ABANDONED

I hereby certify the foregoing to be a true and accurate Driller's Log
of the formations encountered in the above well.

J. M. RUBER CORPORATION

By J. W. Owen
 J. W. Owen
 Geologist

Subscribed and sworn to before me this 18th day of September, 1952.

My commission expires:
 January 28, 1953

RECEIVED
 THE CORPORATION COMMISSION
 CONSERVATION DIVISION

Sarah J. Reed
 Notary Public

PLUGGING
 FILE NO. 28-343-22W-1327
 LOG PAGE 40-1327-27