


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Meade County, Sec. 34 Twp. 33S Rge. 29W (E) (W)  
Location as "NE/CNW/SW" or footage from lines NW SE NW  
Lease Owner Thomas & Brewer Oil & Gas  
Lease Name Vogt Well No. # 1  
Office Address Box 985 Liberal, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed yes 19  
Application for plugging approved yes 19  
Plugging commenced XXXX 7-25-60 19  
Plugging completed 7-31-60 19  
Reason for abandonment of well or producing formation



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Iac Kamp, Jr.  
Producing formation Depth to top Bottom Total Depth of Well 5796' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		5,455'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging commenced 7-25-60. Plugging completed 7-31-60. Measured into total depth, 5796'. Plugged off bottom with 20' of rock up to 5765' and dumped 5 sacks of cement with bailer on rock. Worked and shot casing. Shot 4 1/2" casing at 5455' and worked casing loose. Started pipe, built rack and slide. Pulled and laid down casing. Plugged hole; Mudded hole up to 550' and set 10' rock bridge and dumped 20 sacks of cement. Mudded hole up to 40'. Set a 10' rock bridge and capped the well with 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 4 1960  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Company  
Address Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
Box 221 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 2nd day of August, 1960

My commission expires December 8th, 1963

Kayann Jenkins  
Notary Public.

15-119-10220-0000


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- THOMAS & BREWER  
Farm- Vogt No. 1

SEC. 34 T. 33 R. 29W  
NW SE NW

Total Depth. 5930'  
Comm. 6-11-60 Comp. 7-4-60  
Shot or Treated.  
Contractor. Bennett & Roberts Drig. Co.  
Issued. 4-21-62

County Meade KANSAS



Elevation: 2527'

Production. Dry

CASING:

8 5/8" 1443' cem w/250 sx.  
4 1/2" 5832' cem w/125 sx.

Figures Indicate Bottom of Formations.

surface soil	100
sand	190
blue shale	300
sand & gravel	490
red bed	690
sand streaks	710
shale & shells	985
sand & shale	1340
shale & Anhydrite strks	1435
Anhydrite	1460
red bed & shale	1650
shale & shells	1900
shale & lime streaks	2036
shale	2300
lime & shale	2463
lime	??
chalky lime	3277
lime	3354
chalky lime	3633
lime & shale	3960
shale	4303
lime & shale	4674
lime	5205
lime & shale	5246
lime	5591
lime & shale	5637
lime	5930 RTD
Total Depth	

TOPS: SCOUT

Heebner	4402
Kansas City	4576
Marmaton	5210
Cherokee	5420
Morrow	5732
Morrow Sand	5772
Chester	5807