

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 119-20,491-0000

LEASE NAME CORDES

WELL NUMBER I-36

2310 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 36 TWP. 33 RGE. 29 (E) or (W)

COUNTY Meade

Date Well Completed 5/28/81

Plugging Commenced 10/19/89

Plugging Completed 10/21/89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR MESA OPERATING LIMITED PARTNERSHIP

ADDRESS P.O. BOX 2009, AMARILLO, TEXAS 79189

PHONE# (806) 378-1000 OPERATORS LICENSE NO. 04824

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/19/89 (date)

by Lacey w/Kansas Corporation Commission (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Kansas City/Toronto Depth to Top 4337' Bottom 4941' T.D. 5039'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Kansas City	gas	surf	1530	8 5/8"	1530'	none
Toronto	gas	surf	5039	5 1/2"	5039'	1988.31'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pumped 70 sx cement from 1630' - 1430'; pumped 35 sx cement from 700'-600'; capped with 10 sx from 33'-3'. Welded on steel plate w/name and date using 9.5# mud visc. Retainer @ 2840' w/100 sx "H" below

(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

Name of Plugging Contractor G&N, Inc. dba Proctor's Casing Pullers License No. 30234

Address 6209 Aluma Valley Dr., Oklahoma City, Oklahoma 73121

NOV - 2 1989
11-2-89

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mesa Operating Ltd Partnership

CONSERVATION DIVISION
Wichita, Kansas

STATE OF TEXAS COUNTY OF POTTER, ss.

Carolyn L. McKee

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carolyn L. McKee

(Address) P.O. Box 2009, Amarillo, TX 79189

SUBSCRIBED AND SWORN TO before me this 31st day of October, 19 89

Dwaina Pitts
Notary Public

My Commission Expires:

