

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

CLARK County. Sec. 12 Twp. 34 Rge. 22 (E)W (W)

Location as "NE/CNW&SW" or footage from lines C, NW

Lease Owner Ashland Oil & Refining Co.

Lease Name Randall Well No. 1-12

Office Address P. O. Box 18695, Oklahoma City, Oklahoma 73118

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 8-21 1965

Application for plugging filed 4-3 1967

Application for plugging approved 4-11 1967

Plugging commenced 7-14 1967

Plugging completed 7-18 1967

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production April 1967

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Roy Eling

Producing formation Chester Depth to top 5400 Bottom 5450 Total Depth of Well 5515 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing	wtr	4463	5050	8-5/8	608	
Marmaton	wtr	5050	5198	4-1/2	5515	4827'
Cherokee	wtr	5198	5377			
Morrow	dry	5377	5398			
Chester	oil	5398				

Describe in detail the manner in which the well was plugged; indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set Baker 1 AA 4-1/2" C.T. plug @ 5300' Dumped 2 sacks cement on top of plug.

Shot & pulled 4827' of 4-1/2 casing.

Hole then filled w/mud -- pumped 35 sks of cement to 590' ran line to check top of cement. Dumped 15 sacks of cement to top of surface.

RECEIVED
STATE CORPORATION COMMISSION

AUG 4 1967

Conservation Division

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gayle E. Toland & Co.

Address Box 94336, Oklahoma City, Oklahoma

STATE OF _____, COUNTY OF _____, ss.

_____(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Pat Reynolds.

(Signature) Pat Reynolds, Engineering Clerk

P. O. Box 18695, Oklahoma City, Oklahoma (Address) 73118

SUBSCRIBED AND SWORN TO before me this 2nd day of August, 1967

Donald R. Lunsford
Notary Public.

My commission expires Jan. 11, 1970



15-025-30074-0000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company. ASHLAND OIL & REFINING
Farm. Randall No. 1

SEC. 12 T. 34 R. 22W
CNW/4

Total Depth. 5518
Comm. 7-23-65 Comp. 8-8-65
Shot or Treated.
Contractor. Earl F. Wakefield
Issued. 12-18-65

County Clark
KANSAS



Elevation. 3875' DF

Production. 120 BO, 3 DWPD

CASING:

8 5/8" @ 609' w/450 sx.
4 1/2" @ 5515' w/135 sx.

Figures Indicate Bottom of Formations.

sand & red bed	89
red bed-shales	230
red bed & sand	525
shale & anhydrite	550
shae, sand & anhydrite	849
shale-anhydrite	973
snad	1012
shale-anhydrite	1256
red shale	1630
shale & sand	1988
lime-shale	2690
chalk & shale	2732
lime & shale	3178
lime, chalk, shale	3532
lime & shale	4560
lime	4565
lime & shale	4693
lime	5515
Rotary Total Depth	

RECEIVED
STATE CORPORATION COMMISSION

APR 10 1967

CONSERVATION DIVISION
Wichita, Kansas

TOPS: Scout

Lansing	4463
Marmaton	5050
Cherokee	5198
Morrow Shale	5377
No Sand	
Chester Lime	5398