

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION Sec. 2745-2745

SEC. 15 TWP. 34 RGE. 30

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Adams "E"

Operator Columbia Fuel Corp. Address Likool-Kans.

Field \_\_\_\_\_ County Meade

Total Depth 6270 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 1 3/8 - 655 ft. Circulated with cement.  
9 7/8 casing set at 2662 ft. - 250 sacks of cement  
5 1/2 casing set at 5868 ft. - 300 sacks of cement.  
Plugged back to 4700 ft with cement. Shot off &  
hulled the 5 1/2 casing - Filled hole with mud - Shot off &  
hulled 500 ft of 9 7/8 casing - Set Rock Bridge & 35 sacks  
of cement at 300 ft - mud to 35 ft - Bridge &  
10 sacks of cement at the surface

**PLUGGING**  
FILE SEC-15 T-34 R-30  
BOOK PAGE-107 LINE-3

**RECEIVED**  
STATE CORPORATION COMMISSION  
OCT 17 1951  
District Conservation Agent  
CONSERVATION DIVISION  
Wichita, Kansas  
Date 10-15-51