

*10*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

**RECEIVED**  
STATE CORPORATION COMMISSION

NOV 9 7 1962

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name J. M. Huber

Complete Address: Box 978 Liberal, Kansas

Lease Name Keading Well No. # 1

Location C SW NE Sec. 14 Twp. 34S Rge. (E) (W) 31

County Seward Total Depth 6149'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Daco Well & Lease Service

Address: Borger, Texas License No. # 138

Operation Completed: Hour 11:45AM Day 24 Month 11 Year 62

The Above well was plugged as follows:

13 3/8" 638' Circulated w/cement. 8 5/8" 2553' Circulated w/cement.

5 1/2" 6149' Cemented. Perforations, 3050' to 6149'

All perforations squeeze from 3050' to 6149' Mud, bottom to 1718'

Shot pipe at 1718' Plug and 25 sax.cement at 1718' to 1640'

Mud 1640' to 750' Plug and 35 sax.cement 750' to 640'

Mud 640' to 45' Plug and 15 sax.cement 45' to surface.

Weld cap of surface pipe. No 8 5/8" pipe pulled. No 13 3/8" pipe pulled.

Pulled 1718' 5 1/2" (Company Pump.)

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: J. P. Roberts  
Well Plugging Supervisor

DATE 11/29/62

INV. NO. 6120-W