

15-175-10218-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Shenandoah Oil Corporation

Complete Address Box 1387, Liberal, Kansas

Lease Name Eugene Keating Well No. 1

Location C NE SW Sec. 14 Twp. 34 Rge. 31 (E) (W)

County Seward Total Depth 6150'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Sargents Casing Pulling Co

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 5:00PM Day 29 Month 9 Year 1971

The above well was plugged as follows:

16" to 71' circulated w/ cement. 8 5/8" to 1415' circulated w/ cement.

4 1/2" to 5686' cemented. Top perforations 5342'

Plug bottom w/ 20 sacks cement. Top of cement 5000'

Mud 5000' to 900' Spotted 35 sacks cement 900' to 800'

Mudd 800' to 45' Plug, Hulls & 15 sacks cement 45' to 0'.

Pulled 4572' of 4 1/2" casing. Company Pump

I hereby certify that the above well was plugged as herein stated.

Signed: *Edward J. Evers*
Well Plugging Supervisor

INVOICED

DATE 10/5/71

INV. NO. 4413-w