

15-175-00066-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Wilshire Oil Co.

Complete Address 717 Fidelity Nat'l Bldg., Oklahoma City, Oklahoma

Lease Name Good Well No. 1

Location NW NW Sec. 20 Twp. 34 Rge. 31 (E) (W)

County Seward Total Depth 6441'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sargent Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 3:00PM Day 15 Month 4 Year 1974

The above well was plugged as follows:

13 3/8" to 731' circulated w/ cement. 9 5/8" to 2722' circulated w/ cement.

5 1/2" to 5947' cemented. Top perforations 5936'

Plug bottom w/ 20 sacks cement. Top of cement 5850'

Mud 5850' to 900' Spotted 35 sacks cement 900' to 800'

Mud 800' to 45' Plug, Hulls & 15 sacks cement 45' to 0'.

Company Pump Pulled 3100' of 5 1/2" casing.

INVOICED hereby certify that the above well was plugged as herein stated.

DATE 4/26/74
INV. NO. 8995-W

Signed: [Signature]
Well Plugging Supervisor