

15-175-20618-00-00

RECEIVED  
STATE CORPORATION COMMISSION

KANSAS

FORM CP-3  
Rev. 1-8-82

APR 20 1982

STATE CORPORATION COMMISSION

CONSERVATION DIVISION  
Wichita, Kansas

CONSERVATION DIVISION AGENT REPORT

API Number 15-175-20618 ✓

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Quingue Oil & Gas Production

Complete Address 18 West 3rd St. Liberal, Kansas 67901

Lease Name Begood Well No. 1-20

Location C-S E N W Sec. 20 Twp. 34 Rge. 31 (East) (West)

County Seward Total Depth 6500'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor H. R. G. Drilling Co. Inc.

Address Box 1157, Liberal, Kansas 67901 License No. \_\_\_\_\_

Operation Completed: Hour: 10:30 AM Day: 15 Month: April Year: 19 82

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

The anhydrite was topped at 1485'. 1st plug at 1530' with 70 sky of cement. 2nd plug at 750' with 25 sky of cement. 3rd plug at 40' to 0' on solid bridge with 10 sky of cement. Then they circulated 10 sky of cement in rat hole & 5 sky of cement in mouse hole. The cement was pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by Halliburton Co.

Amount of Surface Casing: 1503' 8 1/2" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul M. Luthi  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

This well was out of my area and had wells in my area to take care of.

Signed: Paul A. Luthi  
Conservation Division Agent

INVOICED  
DATE 4-28-82  
INV. NO. 42-10