

15-175-00098-00-00

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

SEP 18 1961  
9-18-61  
CONSERVATION DIVISION  
KANSAS

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: SEWARD

Location: CNE-NE Sec. 23 Twp. 34 Rge. 31 (E) \_\_\_\_\_ (W)

Name of Field: \_\_\_\_\_ Total Depth: 6300'

I have this date completed supervision of plugging of:

Lease Name: KEATING A Well No. 1

Operator's Full Name: COLUMBIAN FUEL CORP

Complete Address: DRAWER 31 LIBERAL, KANS

Plugging Contractor: DOC LEASE & WELL SERVICE

Address: BORGER, TEXAS License No. 138

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5:00 PM Day 10 Month SEPT Year 1961

The above well was plugged as follows:

13 3/8 - 668 w/150 - 9 7/8 - 2503' w/675 - 5 1/2 - 5397 - TOP PERF 5332'  
PUMPED 15 BU MUD THROUGH TUBING FROM 5377 TO 5120'  
PULLED 3980' 5 1/2" PIPE - FILLED HOLE W/MUD TO 650'  
PULLED 706' 9 7/8" PIPE - PUMPED 35 BU MUD IN 13 3/8"  
FROM 650' TO 610' - MUD TO 20' - BRIDGED - CAPPED W/15  
BU MUD TO BASE OF COLLAR.

Signed: Frank Brundage  
Conservation Division Agent

Reviewed: Harold Steeles  
Field Supervisor

Remarks:

INVOICED

DATE 9/28/61

INV. NO. 3762W