

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 13 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Venus Oil Company

Complete Address 1200 Nat'l Bk of Commerce Bldg., San Antonio, Texas 78205

Lease Name Shafer Heirs Well No. 1

Location NW SE Sec. 2 Twp. 34 Rge. 31 (E) (W)

County Seward Total Depth 6070'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Sargent Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 2:00Pm Day 7 Month 2 Year 1974

The above well was plugged as follows:

10 3/4" to 1349' circulated w/ cement. 7" to 5228' cemented

Top perforations 5119' Plug bottom w/ 25 sacks cement.

Top of cement 5020' Mud 5020' to 800'

Spotted 40 sacks cement 800' to 700' Mud 700' to 35'

Plug, Hulls & 15 sacks cement 35' to 0'. Company Pump

Pulled 2585' of 7" casing.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 2/13/74

Signed: [Signature]  
Well Plugging Supervisor

INV. NO. 8567-W