

15-119-10255-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 4 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Texaco Inc.

Complete Address Box 2420, Tulsa, Oklahoma 74102

Lease Name A & H Adams Unit Well No. 2

Location SE SE Sec. 36 Twp. 34 Rge. 30 (E) (W)

County Meade Total Depth 6430'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated None

Plugging Contractor Sargents Casing Pulling Co.

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 5:00PM Day 27 Month 12 Year 1972

The above well was plugged as follows:

<u>13 3/8" to 413' circulated w/ cement.</u>	<u>9 5/8" to 2864' circulated w/ cement.</u>
<u>7" liner 2651' to 6400' cemented.</u>	<u>Top perforations 5874'</u>
<u>Plug bottom w/ 30 sacks cement.</u>	<u>Top of cement 5770'</u>
<u>Mud 5770' to 2880'</u>	<u>Spotted 90 sacks cement 2880' to 2330'</u>
<u>Mud 2330' to 450'</u>	<u>Spotted 60 sacks cement 450' to 300'</u>
<u>Mud 300' to 40'</u>	<u>Plug, Hulls & 15 sacks cement 40' to 0'.</u>
<u>Company Pump</u>	<u>No pipe pulled.</u>

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Evers
Well Plugging Supervisor

INVOICED
DATE 1/4/73
INV. NO. 6809-10