

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 21 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Thomas Petroleum

Complete Address Box 1177, Liberal, Kansas

Lease Name Fox Well No. #3

Location NE NE SW Sec. 35 Twp. 34 Rge. 30 (E) (W)

County Meade Total Depth 6052'

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Sargents Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 4:00P<sup>M</sup> Day 16 Month 8 Year 1974

The above well was plugged as follows:

8 5/8" to 1445' circulated w/ cement. 5 1/2" to 6024' cemented.

Top perforations 5900' Plug bottom w/ 20 sacks cement.

Top of cement 5740' Mud 5740' to 900'

Spotted 30 sacks cement 900' to 800' Mud 800' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'. Company Pump

Pulled 2740' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated

INVOICED

Signed: Edgar Eves  
Well Plugging Supervisor

DATE 8/22/74

INV. NO. 9750-W