

RECEIVED

OCT 03 2003

KCC WICHITA

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev.03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 119-10239-00-01 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Kaiser-Francis Oil Company KCC LICENSE # 6568
(owner/company name) (operator's)

ADDRESS P. O. Box 21468 CITY Tulsa

STATE OK ZIP CODE 74121-1468 CONTACT PHONE # (918) 491-4314

LEASE Adams Ranch WELL# 1-12 SEC. 12 T. 35S R. 30 (East/West)

- SW - NE - NW SPOT LOCATION/QQQQ COUNTY Meade

990 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1650 FEET (in exact footage) FROM S/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 9 SET AT 1401 CEMENTED WITH 500 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 6314 CEMENTED WITH 100 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perfs: 5168-5172 CIBP @ 6000' w/10' cmt on top.

ELEVATION 2438 T.D. 6540 PBDT 5990 ANHYDRITE DEPTH Unk.
(G.L./~~FEEL~~) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP @ 5000' w/10' cmt on top. Locate free-pt @ approx. 3500' & cut off csg. Spot 20 sxs cmt @ 3450'-3550'. Spot 51 sxs cmt @ 1351'-1451'. Spot 17 sxs cmt from 50'-surface. Cut off WH & install DH marker.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? Yes

If not explain why? Not available in file.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Carroll Fulton, Supt. PHONE# (806) 435-6670

ADDRESS P. O. Box 746 City/State Perryton, TX

PLUGGING CONTRACTOR Kaiser-Francis Oil Company KCC LICENSE # 6568
(company name) (contractor's)

ADDRESS P. O. Box 21468 PHONE # (918) 491-4314

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 10/7/03

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9/30/03 AUTHORIZED OPERATOR/AGENT: C. Jan Valkenburg
(signature)

Charlotte Van Valkenburg

6/04

6/04



CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Kaiser-Francis Oil Co.
PO Box 535528
Tulsa, OK 74153

October 08, 2003

Re: ADAMS RANCH #1-12
API 15-119-10239-00-01
SWNENW 12-35S-30W, 990 FNL 1650 FWL
MEADE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888

Sincerely,

David P. Williams
Production Supervisor