

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections.

Applications must be filed for dual completion, commingling, SWD and injection, T.A.

X Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.).

KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Ladd Petroleum Corporation
ADDRESS P. O. Box 2848
Tulsa, Oklahoma 74101

API NO. 15-129-20,612-0000
COUNTY Morton
FIELD Berryman-Richfield

\*\*CONTACT PERSON L. O. Butner
PHONE (918) 587-6531

PROD. FORMATION Morrow

PURCHASER Diamond Shamrock Corporation
ADDRESS P. O. Box 631
Amarillo, Texas 79173

LEASE Berryman-Richfield Unit (B-RU)

DRILLING CONTRACTOR Rains & Williamson Oil Co., Inc.
ADDRESS 435 Page Court, 220 W. Douglas
Wichita, Kansas 67202

WELL NO. 6-3

WELL LOCATION SE NE
1980 Ft. from North Line and
660 Ft. from East Line of
the NE SEC. 34 TWP. 32S RGE. 41W

PLUGGING CONTRACTOR ADDRESS

WELL FLAT

Grid diagram for well flat with '34' in the center.

KCC KGS (Office Use)

TOTAL DEPTH 5095' PBD 5048'

SPUD DATE 3-11-82 DATE COMPLETED 3-23-82

ELEV: GR 3402' DF KB 3413'

DRILLED WITH (XXXX) (ROTARY) (XXX) TOOLS

Amount of surface pipe set and cemented 1383' DV Tool Used? No

AFFIDAVIT

STATE OF OKLAHOMA, COUNTY OF TULSA SS, I,

L. O. Butner OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS Production Engineer (FOR) Ladd Petroleum Corporation

OPERATOR OF THE Berryman-Richfield Unit LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 6-3 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 18 DAY OF April, 19 82, AND THAT

ALL INFORMATION CONTAINED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIRMS THAT THE FOREGOING IS TRUE AND CORRECT.

STATE RECEIVED APR 20 1982 CONSERVATION DIVISION

(S) L.O. Butner

SUBSCRIBED AND SWORN BEFORE ME THIS 28th DAY OF April, 19 82

Mary E. Russell NOTARY PUBLIC

MY COMMISSION EXPIRES: 1-23-85

\*\*The person who can be reached by phone regarding any questions concerning this information. Within 45 days of completion, a witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

SIDE TWO

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
MORROW SAND	4936	4966		

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	24#	1383'	Class H 65/35 poz.	150 sx 550 sx	2% cc. 6% gel, 3% cc.
Production	7 7/8"	5 1/2"	15.5#	5089	Self Stress Class H	100 sx 75 sx	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4 (80 Shots)	4" Csg. Gun	4938-4964

  

Size	Setting depth	Packer set at
2-7/8"	4895' (SN)	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/2000 gal. 7-1/2% MSR 100 acid	4938 - 4964
Fraced w/28,940 gals SF II & 7000# 100 mesh sd; 44,360# 10-20	4938 - 4964

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
4-12-82	Pumping	

  

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	405 bbls.	None	% Trace	--

Disposition of gas (vented, used on lease or sold) ---

Perforations 4938 - 4964

