


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County. Sec. 25 Twp. 20 Rge. (X) 20 (W)
Location as "NE/CNWxSWx" or footage from lines NW NE NE
Lease Owner Colorado Oil and Gas Corporation
Lease Name NEWSOM Well No. 1
Office Address Box 1030, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed October 31, 19 56
Application for plugging filed August 5, 19 59
Application for plugging approved August 7, 19 59
Plugging commenced August 14, 19 59
Plugging completed August 19, 19 59
Reason for abandonment of well or producing formation Producing formation depleted

If a producing well is abandoned, date of last production July 25, 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Conglomerate Depth to top Bottom Total Depth of Well 4282 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRDM	TD	SIZE	PUT IN	PULLED OUT
				8-5/8"	427'	None
				5-1/2"	4360'	3421'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole to 4282' and found it open. Filled w/sand to 4260' and dumped 5 sacks of cement with bailer. Pulled 5-1/2" casing. Cleaned hole and mudded the hole to 300'. Bailed off fluid, set rock bridge to 290' and dumped 20 sacks of cement. Mudded the hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED...

RECEIVED
STATE CORPORATION COMMISSION

SEP 10 1959
9-10-59
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bill K. Henrichs (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill K. Henrichs
Bill K. Henrichs
Box 1030, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of September, 1959

Helen L. Martin
Helen L. Martin
Notary Public.

My commission expires August 19-1963

PLUGGING
FILE SEC 25 T 20 R 20
BOOK PAGE 58 LINE 2

DRILLERS LOG

15-145-00107-0000

Newsom No. 1
Loc: NW NE NE
Sec: 25-20S-20W
Pawnee County, Kansas
Company: Monaker-Davis Drig. Co., et al
Contractor: Monaker-Davis Drig. Co.

Comm: 9- 6-56
Comp: 9-22-56
Rotary Total Depth: 4428'
Casing: 8-5/8" at 429'
5-1/2" at 4361'

0	80	Sand & Gravel
80	580	Shale
580	685	Red Bed & Sand
685	865	Eyp Rock & Red Bed
865	1345	Red Bed & Shale
1345	1375	Anhydrite
1375	2100	Shale & Shells
2100	2300	Lime & Shale
2300	2360	Shale & Lime
2360	2420	Lime (Sandy)
2420	2740	Lime & Shale
2740	2760	Shale & Lime
2760	3080	Lime & Shale
3080	3190	Shale & Lime
3190	3452	Lime & Shale
3452	3465	Shale & Lime
3465	3500	Lime
3500	3817	Lime & Shale
3817	4015	Lime
4015	4206	Lime & Shale
4206	4220	Sand
4220	4270	Lime & Shale
4270	4305	Lime & Chert
4305	4308	Chert
4308	4428	Lime & Chert
4428		Total Rotary Depth

8-5/8" casing cemented at 429' with 300 sacks and 6 sacks calcium chloride.

RECEIVED
STATE CORPORATION COMMISSION

AUG 6 1959

CONSERVATION DIVISION
Wichita, Kansas

5-1/2" casing cemented at 4361' with 150 sacks cement.

I certify that this is the true and correct copy of the above log to the best of my knowledge.

H. S. Forbes
H. S. Forbes

Subscribed and sworn to before me this 27th day of September, 1956.

Kenneth G. Fischer
Kenneth G. Fischer, Notary Public

My commission expires: 6-25-59

PLUGGING
FILE SEC. 25 T. 22 R. 22W
BOOK PAGE 58 LINE 7