

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

15-175-00382-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Seward SEC. 22 TWP. 34S RGE. 34 E/W  
Location as in quarters or footage from lines:  
2540' FNL & 2535' FWL


Lease Owner Anadarko Production Company  
Lease Name Hacker Well No. 1  
Office Address Box 351, Liberal, Kansas 67901  
Character of Well (Completed as Oil, Gas or Dry Hole): Gas  
Date Well Completed 4/10/50  
Application for plugging filed 9/10/82  
Plugging commenced 10/15/82  
Plugging completed 10/20/82

Reason for abandonment of well or producing formation  
Water encroachment

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation Chase Depth to top 2639 bottom 2751 T.D. 2778

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Chase	Gas	2639	2751	10-3/4"	720'	0
				7"	2639'	0
				5-1/2"	127'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set. Pumped 50 sxs cement to 2551', displaced with drilling mud, spotted 35 sxs from 1200' to 1050', spotted 40 sxs from 750' to 600', spotted 40 sxs from 40' to 3', cut of casing at 3', capped and inscribed well.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Sargents Casing Pullers

STATE OF Kansas COUNTY OF Seward, ss.  
Paul Campbell (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Paul Campbell  
Box 351, Liberal, Kansas 67901  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of November 19 82

My Commission expires: 7/26/83



RECEIVED  
ELIZABETH J. HOOPER  
Notary Public  
NOV 08 1982

CONSERVATION DIVISION  
Wichita, Kansas