


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

CLARK County. Sec. 32 Twp. 34S Rge. 21W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SE NW/4
Lease Owner Sinclair Oil & Gas Company
Lease Name Randall Well No. 1
Office Address P. O. Box 2319, Pampa, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed December 3, 19 60
Application for plugging filed September 7, 19 65
Application for plugging approved September 8, 19 65
Plugging commenced September 13, 19 65
Plugging completed September 16 19 65
Reason for abandonment of well or producing formation Oil Zone Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production July 19 61
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Hugh Scott, Sublett, Kansas
Producing formation Morrow Depth to top 5489' Bottom 5532' Total Depth of Well PB5610' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow (Upper)	Oil	5489'	5501'	20"	226'	0
Morrow (Lower)	Oil	5516'	5532'	10-3/4"	638'	0
				5-1/2"	5680'	3533'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped in 20 sacks cement plug to 4960'. Spotted 50 sacks cement plug at 700' up to 500'. Set 20 sacks cement plug at 50' up to Ground Level or top of surface.

RECEIVED
STATE CORPORATION COMMISSION

SEP 27 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Daco Lease & Well Service
Address 1700 South Main, Borger, Texas, 79007

STATE OF Texas, COUNTY OF Gray, ss.
Geo. W. Crumrine (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Geo. W. Crumrine - Field Supt.
P. O. Box 2319, Pampa, Texas, 79066
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of September, 19 65

My commission expires June 1, 1967

Buck J. Salmon Notary Public.

15-025-10117-0000

RECEIVED
STATE CORPORATION COMMISSION

RANDALL NO. 1

NW/4 of Section 32-34S-21W
Clark County, Kansas
Sinclair Oil & Gas Company

SEP 8 1965

CONSERVATION DIVISION
Wichita, Kansas

20" O. D. casing cemented at 226'
10-3/4" O. D. casing cemented at 638'
5-1/2" O. D. casing cemented at 5680'

Drilling commenced 11-6-60
Drilling completed 12-3-60

FROM	TO	FORMATION	REMARKS
0'	118'	Surface sand & red bed	
118	1050	Red bed	20" O. D. casing cemented with 450 sacks at 226'
1050	1270	Shale	
1270	1535	Shale & shells	10-3/4" O. D. casing cemented with 550 sacks at 638'
1535	1800	Shale	
1800	2140	Anhydrite & shale	
2140	2240	Anhydrite	
2240	2355	Anhydrite & lime	
2355	2664	Anhydrite	Tops: Hoover-Elgin 4085'
2664	2707	Anhydrite & dolomite	Heebner 4281'
2707	2795	Shale	Toronto 4319'
2795	2894	Shale & lime	Lansing 4497'
2894	2965	Lime	Marmaton 5316'
2965	3590	Shale & lime	Cherokee 5352'
3590	3659	Lime & shale	Atoka 5396'
3659	3824	Lime	Morrow(Up) 5491'
3824	3904	Lime & shale	Morrow(Lw) 5516'
3904	4280	Shale	Miss-Chester 5551'
4280	4370	Lime & shale	Miss-St.Gen. 5632'
4370	4531	Shale & lime	
4531	4664	Lime	Perforations:
4664	4726	Lime & chert	Morrow Sand(UP) 5489'---5501'--12'
4726	5343	Lime	Morrow Sand(LW) 5516'---5532'--16'
5343	5405	Lime & shale	
5405	5456	Lime	
5456	5516	Shale, lime & sand	
5516	5554	Lime & sand	
5554	5639	Lime	
5639	5670	Lime & sand	
5670	5685	Lime	5-1/2" O. D. casing cemented with 200 sacks at 5680'

T. D. 5685'

This is a true copy of the driller's log as shown on the drilling tickets.

HARBOR DRILLING COMPANY

By Edith P. P. P.

Subscribed and sworn to before me on this 21st day of December, 1960.

Messrs. Jane P. P.
Notary Public

My commission expires 7-27-61