

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Clark County, Sec. 28 Twp. 34S Rge. 21 (X) (W)

Location as "NE/CNW/SW" or footage from lines C-NE-SW

Lease Owner Texaco Inc.

Lease Name Ella Campbell Unit Well No. 1

Office Address P. O. Box 2420, Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) GAS

Date well completed 12-3-60 19

Application for plugging filed 9-3-75 19

Application for plugging approved 9-4-75 19


Plugging commenced 9-12-75 19

Plugging completed 9-13-75 19

Reason for abandonment of well or producing formation uneconomical

If a producing well is abandoned, date of last production 12-12-74 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Clarence Thomas

Producing formation Morrow Depth to top 5450' Bottom _____ Total Depth of Well 5660 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow	gas			13-3/8"	156'	none
				8-5/8"	609'	none
				2-7/8"	5638'	4100'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back from 5577-5300' w/10 sx cmt, 5300-675' w/hvy mud, 675-575 w/35 sx cmt, 575-200' w/hvy mud, 200-100' w/35 sx cmt, 100-45' w/hvy mud, 45' to 3' below GL, w/15 sx cmt. 3' to surf w/dirt.

PLUGGING COMPLETE

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1975
9-24-75
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service

Address Box 56 506, Liberal, Ks.

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
F. E. ANDERSON (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. E. ANDERSON Oper. Supt.

Box 2420, Tulsa, Ok.

(Address)

SUBSCRIBED AND SWORN to before me this 17th day of Sept., 19 75

My commission expires Nov. 17, 1975

M. K. VANN
M. K. VANN
MY COMMISSION EXPIRES
NOVEMBER 17, 1975

Notary Public.

To Kansas Corporation Commission

From N. E. Morton

Date 9/3/75

Please:

- Attend to
- Note and return
- Note and forward to Files
- See (phone) me re attached

- Prepare reply for my signature
- Send me information required to answer
- For your information
- As per conversation

- As requested
- For your comments and suggestions
- Does attached meet with your approval?
- For signature, if you approve

Other Remarks

We mailed to your office, this date, an application for permit to plug the Ella Campbell Unit #1, Section 28-34S-21W, Clark County, Kansas. The well log was inadvertently omitted and was not attached to application when mailed.

Enclosed is well log for this well.

RECEIVED
STATE CORPORATION COMMISSION

SEP 04 1975

CONSERVATION DIVISION
Wichita, Kansas

15-025-10133-0000

LEASE: ELLA CAMPBELL UNIT #1
OPERATOR: TEXACO INC.
CONTRACTOR: EARL F. WAKEFIELD
COMD: 10-27-60 COMP: 11-17-60

LOCATION: C NE SW
SECTION 28-34S-21W
CLARK COUNTY, KANSAS
CASINO: 13 3/8" Set at 156'
8 5/8" Set at 609'
2 7/8" Set at 5698'

Red Bed and Cyp	99
Shells and Red Bed	158
Red Bed and Shale	198
Broken Shale and Red Bed	500
Shells and Red Bed	610
Red Bed	977
Red Bed Lime	1270
Shale and Shells	2195
Shale and Lime Streaks	2221
Anhydrite, Lime and Shale	2325
Lime, Shale with streaks anhydrite	2395
Shale & streaks of Anhy. & Little lime	2525
Lime and Shale	3018
Sandy Lime, Shale and Lime	3133
Lime and Shale	3888
Shale	4018
Shale and Lime	4405
Lime and Shale	4536
Shale and Lime	4569
Lime	4642
Lime and Chert	4661
Cherty Lime	4710
Lime	5285
Lime and Shale	5392
Lime	5435
Lime and Shale	5518
Lime	5588
Lime and Shale	5612
Lime	5660
T. D.	5660

RECEIVED
STATE CORPORATION COMMISSION

SEP 04 1975

STATS OF KANSAS)
)
COUNTY OF SEDGWICK)

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above is a true and correct copy of the log on the Ella Campbell Unit #1 well, located C NE SW of Section 28-34S-21W, Clark County, Kansas.

EARL F. WAKEFIELD

Fred J. Backus

Subscribed and sworn before me this 22nd day of November, 1960

C. A. SNOW
C. A. SNOW NOTARY PUBLIC

My commission expires July 26, 1962.