

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Clark County, Sec. 27 Twp. 34S Rge. 21W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW-NE

Lease Owner Sunray Mid-Continent Oil Company

Lease Name Ella Campbell Well No. 1

Office Address Box # 788, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 16, 19 56

Application for plugging filed April 20, 19 56

Application for plugging approved April 23, 19 56


Plugging commenced April 23, 19 56

Plugging completed April 25, 19 56

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Merle Rives

Producing formation Depth to top Bottom Total Depth of Well 5650' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				16" OD	160'	None
				8 5/8"	2438'	1680'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

The hole was filled with mud to bottom of 8 5/8" casing at 2438' and 50 sacks of cement spotted. Pulled casing out, mudded the hole to 100', set a 10' rock bridge and ran 30 sacks of cement. Mudded hole to 155', set 10' rock bridge and ran 20 sacks of cement. Mudded the hole to 15' set rock bridge and ran 10 sacks of cement to base of cellar. Plugging completed

RECEIVED  
STATE CORPORATION COMMISSION  
APR 28 1956  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company

Address Chase, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Norman E. Montgomery (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Norman E. Montgomery

Box # 788, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27 day of April, 19 56

My commission expires Dec. 24, 1956

Notary Public.

PLUGGING  
FILE SEC 27 T 34 R 21W  
BOOK PAGE 55 LINE 36

Sunray Mid-Continent Oil Company  
Tulsa, Oklahoma

Tulsa, Oklahoma  
April 23, 1956

CONTRACTOR: Stickle Drilling Company  
Drilling Commenced: March 16, 1956  
Drilling Completed: April 18, 1956

Ella Campbell #1 - N/2  
and SW/4 of Sec. 27-34S-  
21W, Clark County, Kansas.

DRILLERS LOG

Depth Figures Indicate base of Formation

Sand	40
Sand Red Bed	400
Shale & Shells	550
Red Bed & Shells	775
Shale & Shells	950
Anhydrite	995
Shale & Shells	1175
Lime & Shale	1650
Shale & Shells	1855
Shale & Lime Shells	1945
Shale & Shells	1955
Anhydrite - 2nd	2005
Lime & Shale	2050
Shale & Lime	2155
Lime & Shale	2355
Lime	2385
Lime & Shale	2449
Lime	2530
Lime & Shale	2640
Lime	2800
Lime & Shale	2900
Shale & Lime	3010
Lime	3130
Lime & Shale	3370
Lime	3480
Shale & Lime	3610
Lime	3760
Lime & Shale	3806
Shale & Lime	3910
Lime & Shale	4000
Shale & Lime	4470
Shale	4498
Lime, K.C.	4545
Lime & Sand	4600
Lime K.C.	4635
Lime	4729
Lime & Shale	4790
Lime	5015
Marmaton	5061
Lime & Shale	5319
Cherokee	5350
Shale	5445
Shale & Lime	5514
Narrow	5600
Mississippi	5643
Lime	5650 TD

RECEIVED  
STATE CORPORATION COMMISSION  
APR 28 1956  
CONSERVATION DIVISION  
Wichita, Kansas

I, Frank E. Stickle, hereby certify the above to be a true and complete Drillers Log of Sunray Mid-Continent Oil Company's Ella Campbell #1, N/2 and SW/4 of Section 27-34S-21W, Clark County, Kansas.

Frank E. Stickle  
Frank E. Stickle

Lillian T. Bonham  
Notary Public

February 13, 1960  
My Commission Expires

**PLUGGING**  
FILE SEC 27-34-21W  
BOOK PAGE 55 LINE 36