


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Pratt County. Sec. 34 Twp. 28 Rge. 12 (E) W (W)

Location as "NE/CNW/SE/SW" or footage from lines NW NW NW  
Lease Owner McKnab Drilling, Inc.  
Lease Name Banbury Well No. 1  
Office Address 503 Union National Bank Bldg. - Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 1, 1956  
Application for plugging filed July 1, 1956  
Application for plugging approved July 1, 1956  
Plugging commenced July 1, 1956  
Plugging completed July 1, 1956  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rivas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	324	8-5/8"	6-11-56	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Gunned up pits. Circulated heavy mud until returned. Layed down drill pipe. Filled hole w/ mud to 300'. Set Howco top plug with 1/3 sack hulls at 300'. Placed 20 sacks cement through 10 jts. drill pipe. Filled hole with mud to 35' and set Howco top plug w/ 1/3 sack hulls at 35'. Placed 10 sacks cement on plug. Filled to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_  
Address \_\_\_\_\_

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Don Gardner (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
503 Union National Bank Bldg. - Wichita  
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of July, 19 56

My commission expires July 28, 1958

Charlenne Barlowe  
Notary Public.

PLUGGING  
FILE SEC. 34 T. 28 R. 12 W  
BOOK PAGE 77 LINE 12

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 07 1956

COMPANY: McKnab Drilling, Inc.  
 503 Union National Bank Building  
 Wichita, Kansas

LOCATION: Banbury #1  
 NW NW NW 34-28-12  
 Pratt County, Kansas

CONTRACTOR: McKnab Drilling, Inc.  
 503 Union National Bank Building  
 Wichita, Kansas

CASING RECORD: 8-5/8" surface set @ 324' with 285 sacks cement

DRILLER'S LOG

<u>FROM</u>	<u>TO</u>		
0	100	Surface Clay & Shale	COMMENCED: 6-9-56
100	260	Sand	
260	640	Shale, Red Bed & Shells	
640	865	Shale & Stks. of Gyp	
865	1005	Red Bed	
1005	1095	Shale & Cky Lime	
1095	710	Reamed 12-1/4"	
710	1560	Shale & Shells	
1560	2075	Lime & Shale	
2075	2335	Shale & Lime	
2335	2410	Shale	
2410	2720	Shale & Lime	
2720	2820	Shale	
2820	3155	Shale & Lime	
3155	3265	Shale	
3265	3475	Shale & Lime	
3475	3751	Lime & Shale	
3751	4250	Lime	
4250	4260	Chert & Lime	
4260	4310	Lime	
4310	4345	Shale	
4345	4374	Shale & Chert	
4374	4400	Shale, Lime & Chert	
4400	4425	Chert, Lime & Shale	
4425	4448	Chert & Lime	
4448	4470	Lime & Shale	
4470	4493	Lime, Shale & Chert	
4493	4501	Sand, Lime & Shale	
4501	4510	Simpson	
	4510	Rotary Total Depth	

The undersigned, Don Gardner, Secretary-Treasurer of McKnab Drilling, Inc., hereby certifies in behalf of said company, that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the daily drilling reports.

McKNAB DRILLING, INC.

PLUGGING  
 FILE SEC 34 T 28 R 12W  
 BOOK PAGE 77 LINE 12

EM:

*Don Gardner*  
 Don Gardner

Subscribed and sworn to before me this 5th day of July, 1956.

*Christine Backhaus*  
 Notary Public

JUL 7 - 1956

CONSERVATION DIVISION  
 Wichita, Kansas

My Commission Expires: July 28, 1958.