


9

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Flat

Pratt County, Sec. 34 Twp. 28S Rge. 12W(E) (W)
Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner W. C. Payne and Price Exploration Company
Lease Name Georgia Well No. 1
Office Address 800 United Founders Tower, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 24 19 67
Application for plugging filed August 24 19 67
Application for plugging approved August 25 19 67
Plugging commenced August 25 19 67
Plugging completed August 25 19 67
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Archie Elving
Producing formation None Depth to top Bottom Total Depth of Well 4483 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
						None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Drilling mud @ 300'. Mixed and dumped one-half sack of hulls and 20 sacks of cement. Filled surface casing to 40' with drilling mud. Mixed and dumped one-half sack of hulls and 8 sacks of cement. Mixed and set 2 sack cement plug in top of mouse hole and rat hole. Job complete @ 1:30 a.m., August 25, 1967.

RECEIVED
STATE CORPORATION COMMISSION
SEP 1 1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Garvey Drilling Company
Address Route #2, Great Bend, Kansas

STATE OF OKLAHOMA, COUNTY OF OKLAHOMA, ss.
W. C. Payne (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____

800 United Founders Tower, Okla. City, Okla. (Address)

SUBSCRIBED AND SWORN TO before me this 31st day of August, 1967

Paula J. Pitman
Notary Public.

My commission expires July 1, 1970

WELL LOG

COMPANY **W. C. Payne**

SEC. 34 T. 28S R. 12W

FARM **Georgia**

NO. **1**

LOC. **NE SW**


TOTAL DEPTH **4484'**

COUNTY **Pratt**

COMM. **8-12-67**

COMP. **8-24-67**

CONTRACTOR **Garvey Drilling Company**



CASING **8 5/8" @ 370' w/350 SX**

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1967

CONSERVATION DIVISION
Wichita, Kansas

ELEVATION
PRODUCTION **D & A**

FIGURES INDICATE BOTH DEPTHS AND FORMATIONS

- 68' Native Soil
- 270' Sand
- 732' Red Bed
- 735' Anhydrite
- 842' Red Bed and Shale
- 1004' Anhydrite and Shale
- 1732' Shale, Salt and Shells
- 1805' Shale and Lime
- 2530' Lime and Shale
- 2773' Shale and Lime
- 3646' Lime and Shale
- 3780' Shale
- 4223' Lime
- 4235' Lime and Shale
- 4268' Chert and Lime
- 4309' Lime
- 4377' Shale
- 4410' Cherty Lime
- 4430' Lime
- 4479' Cherty Lime
- 4484' Sand
- 4484' RTD

State of Kansas

County of Barton

SS

I, Sam N. Stephens

of

Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Georgia No. 1 well.

Sam N. Stephens

Subscribed and sworn to before me this 29th day of August 19 67

My Commission Expires: November 5th, 1969

Richard Doy
NOTARY PUBLIC