

15-129-00152-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Finney State Office Building  
130 South Market, Rm 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER NA (SPUD 10/19/64)

LEASE NAME INTERSTATE "I"

WELL NUMBER 2

1980 Ft. from S Section Line

660 Ft. from W Section Line

SEC. 10 TWP. 34S RGE 43 ( E ) or ( W )

COUNTY MORTON

Date Well Completed 11/13/64

Plugging Commenced 04/17/97

Plugging Completed 04/18/97

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 04/03/97 (date)

by MR. STEVE MIDDLETON (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation RED CAVE Depth to Top 1290' Bottom 1293' T.D. 5130'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
RED CAVE	GAS	1290'	1293'	8-5/8"	1265'	4'
				4-1/2"	1365'	706'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.  
MIRU SARGENTS. PMP CMT PLG FROM 1293-1035 W/20 SXS CMT W/2 SXS HULLS. PULL FREE PT & SHOOT OFF 4-1/2 CSG @ 706. CIRC HOLE W/9 PPG MUD. PULL CSG TO 200'. PMP CMT PLG FROM 200-65' W/40 SXS CMT. PULL CSG TO 40'. PMP CMT PLG FROM 40'-SF W/10 SXS CMT POH W/CSG CUT OFF & CAP 8-5/8 CSG 4' BELOW GL. NOTIFIED KCC REP STEVE MIDDLETON 4/17/97.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John A. Broman

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 14th day of July, 1997.

Shirley J. Childers  
Notary Public

My Commission Expires: \_\_\_\_\_

