

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 10 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name An-Son Corporation

Complete Address 3814 North Santa Fe, Oklahoma City, Oklahoma 73118

Lease Name Fincham Well No. 1

Location C SE NW Sec. 3 Twp. 35 Rge. 33 (EX) (W)

County Seward Total Depth 6304'

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Lillard Casing Pulling

Address Woodard, Oklahoma License No. 618

Operation Completed: Hour 4:00PM Day 3 Month 4 Year 1974

The above well was plugged as follows:

8 5/8" to 1576' circulated w/ cement. 4 1/2" to 6302' cemented.

Top perforations 6218' plug bottom w/ 35 sacks cement.

Top of cement 6100' Mud 6100' to 1625'

Spotted 59 sacks cement 1625' to 1525' Mud 1525' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'. Company Pump

Pulled 1785' of 4 1/2" casing.

**INVOICED**

I hereby certify that the above well was plugged as herein stated.

DATE 4/11/74

INV. NO. 8915-W

Signed: [Signature]  
Well Plugging Supervisor