

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 50-6

LOCATION SWSWSW

SEC. 7 TWP. 35 RGE. 29W

Dry Hole - Abandoned Oil Well - Abandoned Gas Well yes

I have today completed supervision of plugging of:

Well No. 1 Lease Horace G. Adams.

Operator Standolin Oil Co Address Jenith, Kan

Field - County Mead.

Total Depth 6657 Feet.

(Describe briefly the manner in which the well was plugged)

The hole was plugged back 6657 ft to
4675 ft Lane plug & cement. Heavy mud
4675 ft to 400 ft cement 400 ft to 370 ft
35 sax heavy mud 370 ft to 100 ft cement
100 ft to 70 ft 10 sax heavy mud 70 ft to
10 ft cement into base of cellar 14 sax
773 ft of 13 3/8 pipe cemented & left in hole

H. W. [Signature]
District Conservation Agent

PLUGGING
FILE SEC 7 35 R 29W date
BOOK PAGE 50 LINE 6

