

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION Center NE NW

SEC. 6 TWP. 35 RGE. 29 W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. G 1 Lease Adams A. G.

Operator Columbian Fuel Corporation Address Box 994, Liberal, Kansas

Field _____ County Meade

Total Depth 6250 Feet.

(Describe briefly the manner in which the well was plugged)

Hole filled from 6250 to 5314 (5 1/2 casing point) with mud.

Pumped 25 sacks of cement into perforations 5247 5251' left top of cement at 5107' in 5 1/2 casing.

- 5107 to 815' Mud
 - ~~815 to 805' Cement plug~~
 - 805 to 250' heavy mud
 - ~~250 to 240' rock bridge~~
 - 240 to 178' cement plug 25 sacks
 - ~~178 to 35' heavy mud~~
 - 35 to 30' rock bridge
 - ~~30 to top of casing 15 sacks of cement~~
- Top of casing cut off 4' below ground level, ground was leveled.

REC
STATE CORP. DIV.
DEC 12 1951
CONSERVATION DIVISION
Wichita, Kansas

R. J. Phillippe
District Conservation Agent
Date November 30, 1951