

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-119-20,255-0000

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name R. Clay Underwood (R.agon E. Dullin Production Manager)

Complete Address Suit 400, Oil & Gas Bldg., Wichita Falls, Texas

Lease Name H. C. Adams Well No. F-9

Location 70'E + 70S CNW Sec. 3 Twp. 35S Rge. 29W (East) (West)

County Meade Total Depth 6300'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sargants Casing Pulling Service

Address 620 Lincoln, Box 506 Liberal Kansas 67901 License No. 511

Operation Completed: Hour: 5:00 PM Day: 30 Month: September Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

There is 1528' of 8 5/8" surface casing cement circulated with 750 lbs of cement.
There is 6250' of 5 1/2" pipe cemented with 450 lbs cement fill up outside pipe 4130'
The perforations are at 4491' to 4500' with cast iron bridge at 4530'.
1st plug at 4200' with heavy fill mud mix, & 30 lbs of cement tabs.
2nd plug at 1520' with mud mix & 50 lbs of cement. 3rd plug at
40' to 0' on solid bridge with fill mix and 10 lbs of cement.
Plugging accomplished by Sargants Casing Pulling Service
out of Liberal Kans. They pumped the cement down.
They recovered 2618' of 5 1/2" in production pipe.

I hereby certify that the above well was plugged as herein stated.

DATE 10/6/81

Signed: Paul Luthin
Conservation Division Agent

INV. NO. 7802-W

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1981
CONSERVATION DIVISION
Wichita, Kansas