

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 20 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Dellinger of Knight Casing Pulling has this  
date requested permission to plug the following described well:

Mr. Dellinger guarantees payment of the plugging fee.

Operator's full Name: Knight Casing Pulling Co., Inc.

Complete Address: Box 405, Chase, Kansas

Lease Name: Campbell-Harper Trust Well No. 1

Location: SW SW NE Sec. 29 Twp. 34 Rge. 21 (E)(W)

County Clark Total Depth 5637' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Dellinger was instructed to plug the well as follows:

20" to 248' circulated w/ cement, 10" to 608' circulated w/ cement.


5 1/2" to 5620' cemented. Top perforations 5441'

Plug bottom w/ Sand & 5 sacks cement Top of cement 5200'

Mud 5200' to 600' Spotted 50 sacks cement 600' to 500'

Mud 500' to 60' Rock Bridge & 15 sacks cement 60' to 0'

Very truly yours,

  
Conservation Division Agent