

R

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

AUG 25 1967

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Intent to Drill;
 filed August 14, 1967.

Dear Sir:

Mr. Norman Thompson of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: W. C. Payne & Price Exploration Company

Complete Address: 800 United Founders Tower, Oklahoma City, Oklahoma

Lease Name: Georgia Well No. # 1

Location: C NE SW Sec. 34 Twp. 28 Rge. 12 (E) (W) W

County Pratt Total Depth 4483' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Thompson was instructed to plug the well as follows:

378' of 8 5/8" surface pipe, cement circulated with 350 sacks. Fill hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 20 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 8 sacks to base of cellar. Bridge and cement rat hole with 2 sacks. These plugging orders were given by Howard Hess, Winfield, Ks.

Very truly yours,

Audie Elving
 Conservation Division Agent