



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

### State Corporation Commission

#### CONSERVATION DIVISION (Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

DEC - 8 1981  
12-8-81  
CONSERVATION DIVISION  
Wichita, Kansas

#### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Bill Young of Sage Drilling Co has this date requested permission to plug the following described well:

Operator's Full Name: Lee Banks Oil Co.

Complete Address: 200 West Douglas #550 Wichita Kansas 67202

Lease Name: Reist Well No. 1-31

Location: 1-31 Sec. 31 Twp. 34S Rge. 27W(E) (M)

County: Madison Total Depth: 6132'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Young was instructed to plug the well as follows:

There is 140' of 8 5/8" surface casing cement circulated. The anhydrite was topped at 1395'. 1st plug at 1600' with 10 bby of cement. 2nd plug at 1380' push rubber plug to this depth and pump 40 bby of cement on top of it. 3rd plug at 40' to 0' on solid bridge with 10 bby of cement. Then pumped 5 bby each in rat hole & mouse hole. Plugging accomplished by Halliburton Co. out of Liberal Kans.

Very truly yours,

Paul Luttich  
Conservation Division Agent