

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 18 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Huber has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: J.M. Huber Corporation

Complete Address: Box 831, Borger, Texas

Lease Name: Rodgers Unit Well No. 1

Location: C NE Sec. 24 Twp. 34 Rge. 27 (E)(W)

County: Meade Total Depth 6206' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1422' circulated w/ cement. 5 1/2" to 6205' cemented.

Top perforations 5986' Plug bottom w/ 40 sacks cement.

Top of cement 5750' Mud 5750' to 900'

Spot 30 sacks cement 900' to 800' Mud 800' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,


Conservation Division Agent