

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

APR 1 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Dean of Skelly Oil Company has this

date requested permission to plug the following described well:

Mr. Dean guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company

Complete Address: 1020 North Main. Hutchinson, Kansas

Lease Name: Charles Merkle Well No. # 1

Location: App. C-NW Sec. 15 Twp. 34 Rge. 27 (E/W)

County Meade Total Depth 6090' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dean was instructed to plug the well as follows:

8 5/8" 1386' Circulated w/cement. 4 1/2"-4801' Cemented.

Plug back to 4760' Top perforations-4727'

Sand 4760' to 4700' 2 Sax.cement 4700' to 4676'

Mud 4676' to 710' Rock bridge 710' to 700'

35 Sax.cement 700' to 600' Mud 600' to 50' Rock bridge 50' to 40'

15 Sax.cement 40' to surface.

Very truly yours,

Hugh Scott
 Conservation Division Agent