

15-119-10253-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM

(File One Copy)

API NUMBER 15-119-10253-00-00 D&C 03-06-58 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Gulf Oil Corporation OPERATORS LICENSE NO. 5816

(*) ADDRESS P.O. Box 12116, Oklahoma City, OK 73157 PHONE # (405) 949-7000
1320' FNL

LEASE (FARM) Mary Taylor WELL NO. 1 WELL LOCATION 1320' FEL COUNTY Meade

SEC. 33 TWP. 34S RGE. 26 (E) or (W) (W) TOTAL DEPTH 6260' PLUG BACK TD 6100'

Check One:

OIL WELL _____ GAS WELL X D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 1084' CEMENTED WITH 800 SACKS

CASING SIZE 4 1/2" SET AT 6260' CEMENTED WITH 175 SACKS

PERFORATED AT 6010-6024' in MORROW

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Shown on back of form.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN As Soon As Possible

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH R.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: Mr. C. T. Oglesby PHONE # (316) 265-3169
RECEIVED STATE CORPORATION COMMISSION

ADDRESS P.O. Box 2063 - Wichita, KS 67201

PLUGGING CONTRACTOR Reeves & Wilson, Inc. LICENSE NO. #273-Okla
FEB 27 1985
2-27-85
Wichita, Kansas

ADDRESS P.O. Box 963, Woodward, OK 73802 PHONE # (405) 256-6023

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Dorretta Moore
(Operator or Agent)

(*) Please mail approval to
Dorretta Moore at the
address above.

DATE: February 25, 1985

PROCEDURE TO
PLUG & ABANDON

MARY TAYLOR No 1
C NE/4 SEC 33-3-3-23W
MEADE COUNTY, KANSAS

1. NOTIFY STATE PLUGGER BEFORE BEGINNING WORK.
(KCC DISTRICT I - STEVE DURANT / 316-225-6760)
2. MIRU WSU. KILL WELL AS NECESSARY. ND TREE.
NU BOP. POH w/ $2\frac{3}{8}$ " OD TBG.
3. MIRU N. L. McCULLOUGH. RIH w/ $4\frac{1}{2}$ " GR & JB
TO 5990'. RIH w/ $4\frac{1}{2}$ " CIBP & SET @ 5980'.
Dump 2 SKS CMT ON CIBP w/ DUMP BAKER.
RDMD McCULLOUGH.
4. RIH w/ $2\frac{3}{8}$ " OD TBG & TAG BTM PLUG. CIRC
HOLE w/ 9.0 ppg API 36 VISC MUD. POH w/
TBG. RDMD WSU.
5. MIRU CASING PULLERS. FIND FREE POINT OF
 $4\frac{1}{2}$ " OD 9.5' / FT I-55 CSG. SHOOT & PULL
CSG, KEEPING HOLE FULL OFF 9.0 ppg MUD. (Toc @ 5710)
6. MIRU DOWELL. SPOT 50 SKS CL "H" CMT
ACROSS SFC CSG SHOE f/ 1184' TO 1000' WHILE
PULLING OUT OF HOLE w/ CSG. SPOT INTERMEDIATE
PLUG f/ 500' TO 400' w/ 30 SKS CL "H" CMT.
FILL SFC CSG f/ 50' TO 3' BELOW GL w/ 15
SKS CL "H" CMT.
7. CUT OFF SFC CSG 3' BELOW GL. CAP & ID WELL.
8. LEVEL & RESTORE LOCATION.

RECOMMENDED JTB PJC
APPROVED _____

ESD
12-26-84

State of Kansas



HN CARLIN
 CHAEL LENNEN
 ARGALEE WRIGHT
 ITH R. HENLEY
 DITH A. McCONNELL
 AN J. MCLINE

Governor
 Chairman
 Commissioner
 Commissioner
 Executive Secretary
 General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 200 Colorado Derby Building
 202 West 1st Street
 WICHITA, KANSAS 67202-1286

THIS NOTICE

MAY 27 1985

EXPIRES

February 27, 1985

WELL PLUGGING NOTICE

Mary Taylor #1
 1320' FNL 1320' FEL
 Sec. 33-34S-26W
 Meade County

Gulf Oil Corporation
 P. O. Box 12116
 Oklahoma City, OK 73157

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson

William R. Bryson, Director

Please submit your proposal for plugging the above captioned well to

DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760

five days prior to plugging the well (KAR-82-3-113).