

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM

0000 (PLEASE TYPE FORM and File ONE Copy)

API # 15 119 20626 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate spud or completion date.

WELL OPERATOR Texaco F & P, Inc. KCC LICENSE # 4742 ^{12/96}
(owner/company name) (operator's)

ADDRESS P.O. Box 2700 CITY Pampa

STATE TX ZIP CODE 79066-2700 CONTACT PHONE # (806) 669-8456

LEASE J. L. Beall WELL # 2 SEC. 29 T. 34S R. 26W (East/West)

SW - NE - SW SPOT LOCATION/QQQQ COUNTY Meade

1400 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

3480 FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET # _____

CONDUCTOR CASING SIZE 16" SET AT 85' CEMENTED WITH 8 yd. Grout 3 SACKS

SURFACE CASING SIZE 8-5/8" SET AT 1,318' CEMENTED WITH 820 SACKS

PRODUCTION CASING SIZE 4-1/2" SET AT 6,199' CEMENTED WITH 365 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: See Attached

ELEVATION 2337 G. L. T.D. 6,200' PBSD 6,150' ANHYDRITE DEPTH 1331'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR KANSAS CORPORATION COMMISSION JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING See Attached

RECEIVED
5-15-96
MAY 15 1996

CONSERVATION DIVISION

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS.

John Robertson/Bill Hacker PHONE # (405) 338-6820

ADDRESS P.O. Box 631 City/State Guymon, Oklahoma 73942

PLUGGING CONTRATOR Dowell KCC LICENSE # _____
(company name) (contractor's)

ADDRESS P.O. Box 1254, Perryton, TX 79070 PHONE # (806) 435-5436

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Not known at this time

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 5/13/96 AUTHORIZED OPERATOR/AGENT: John D. Allen
(signature)

J. L. BEALL #2
SW-NE-SW
SEC. 29-34S-26W
MEADE COUNTY

(ATTACHMENT TO FORM CP-1)

15-119-20626-0000

PERFORATIONS AND BRIDGE PLUGS:

PERFORATIONS: 6036'-39', 6041'-45' (MORROW), 6080'-85' (CHESTER)

CIBP @ 6020' W/1 SACK CEMENT TO 6007'

PERFORATIONS: 5510'-18' (MARMATON)

4 SQUEEZE HOLES @ 3350'-81' (SQUEEZED W/100 SACKS CEMENT)

EZSV CEMENT RETAINER @ 3310'

4 SQUEEZE HOLES @ 3255' (SQUEEZED W/50 SACKS CEMENT)

4 SQUEEZE HOLES @ 3214' (SQUEEZED W/50 SACKS CEMENT)

PERFORATIONS - 3158'-63', 3198'-3203' (COUNCIL GROVE)

TOP OF CEMENT @ 3016' (CEMENT BOND LOG)

PROPOSED METHOD OF PLUGGING:

PUMP 50 SACKS OF 60/40 POZ W/6% GEL INTO PERFS @ 3158'-63' & 3198'-3203' PLUS CAPACITY OF 4-1/2" CASING (170 SACKS). LEAVE 4-1/2" CASING FULL TO SURFACE. PUMP 248 SACKS 60/40 POZ W/6% GEL DOWN 8-5/8" X 4-1/2" ANNULUS TO 1331'. CUT OFF & CAP CSG. BELOW PLOW DEPTH AND RECLAIM LOCATION.

PLUGGING METHOD RECOMMENDED BY STEVE DURANT KCC/DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 15 1996

CONSERVATION DIVISION
WICHITA, KS



15-119-20626-0000

Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

May 15, 1996

Texaco E & P Inc
P O Box 2700
Pampa TX 79066-2700

J. L. Beall #2
API 15-119-20,626
1400 FSL 3480 FEL
Sec. 29-34S-26W
Meade County

Dear John Robertson/Bill Hacker,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,
David P. Williams

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760