

15-119-10225-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas


96

WELL PLUGGING RECORD

Meade County, Sec. 13 Twp. 34 Rge. (E) 26 (W)

Location as "NE/CNW/SW" or footage from lines. C SW/4
Lease Owner Atlantic Refining Company
Lease Name Wasterday Gas Unit #1 Well No. 1
Office Address 830 Kennedy Bldg. -Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 7-17 1961
Plugging completed 7-21 1961
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5916 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	1209'	none
				4 1/2"	5915'	4099'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Toy Perforation 5715'

Sanded hole to 5700'-dumped 5 sks cement-
mudded hole to 400'-set 10' rock bridge-
dumped 20 sks cement-mudded hole to 50'-
set 10' rock bridge-dumped 10 sks cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 8 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D Casing Pulling Co. License #236
Address Box 572, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Nathan Meltzer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Nathan Meltzer
Drawer "B" Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7 day of August, 1961

Anne Meltzer
Notary Public.
My commission expires 3-30-65



CONTRACTOR'S WELL LOG

COMPANY: Atlantic Refining Company
 CONTRACTOR: Musgrove Petroleum Corp.
 FARM: EASTERDAY #1
 LOCATION: C SW/4 Section 13-34-26W
 Meade County, Kansas
 COMMENCED: November 9, 1956
 COMPLETED: December 9, 1956

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 28 1961
 CONSERVATION DIVISION
 Wichita, Kansas

0	110	Top soil
110	370	Red bed & shale
370	525	Red bed, shale & shells
525	745	Lime shells
745	950	Lime shells & shale
950	1065	Lime & shale
1065	1215	Lime
1215	1370	Shale & shells
1370	1645	Shale & lime shells
1645	1885	Sandy lime & shale
1885	2252	Lime & shale
2252	2376	Lime, shale & gyp
2376	2957	Lime
2957	3140	Lime & shale
3140	3267	Lime
3267	3334	Lime & shale
3334	3623	Lime
3623	3780	Lime & shale
3780	4090	Lime
4090	4388	Lime & shale
4388	5090	Lime
5090	5130	Lime & shale
5130	5179	Lime
5179	5215	Lime & shale
5215	5292	Lime
5292	5324	Lime & shale
5394	5696	Lime
5696	5778	Lime & shale
5778	5822	Lime
5822	5848	Lime & shale
5848	5920	Lime
	5920	Rotary Total Depth

Set 7" surface casing at 1209' with 600 sacks cement.
 Set 4-1/2" pipe at 5916' with 150 sacks cement, plus 4% calcium chloride.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the EASTERDAY #1, C SW/4, Section 13-34-26W, Meade County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION
 BY Gordon L. Koelling
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 12th day of December, 1956.

Reah Joyce Helke
 Notary Public

My commission expires June 16, 1959.

RECORDED

RECEIVED