

15-119-10246-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Meade County, Sec. 12 Twp. 34 Rge. 26 (X) (W)

Location as "NE/CNW/SW" or footage from lines CW/2

Lease Owner Graham-Michaelis Drlg. Co.

Lease Name Theis "A" Well No. #1

Office Address 211 North Broadway

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed 6/15/58 19

Application for plugging filed 5/29/58 19

Application for plugging approved 5/29/58 19

Plugging commenced 6/9/58 19

Plugging completed 6/15/58 19

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5830\* Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Red med. anh</u>			<u>1157</u>	<u>8 5/8"</u>	<u>1157*</u>	
<u>Lime</u>			<u>5830</u>	<u>5 1/2"</u>	<u>5829*</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled back with sand from 5720\* to 5660\* Mixed and dumped 5 sks cement. Loaded hole with mud circulated Set 10\* rock bridge 550\* dumped 20 sks cement Filled hole with mud to 35\* Set 10\* rock bridge 35\* Mixed and dumped 10 sks cement to base of cellar

RECEIVED  
STATE CORPORATION COMMISSION

JUN 25 1958 6-25-58

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.

Address P.O. Box 364 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. O.W. Woodland (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Graham-Michaelis Drlg. Co.

(Signature) O.W. Woodland

211 North Broadway - Wichita, Kans.  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 19 58

T.D. Grier

Notary Public.

My commission expires 1-7-61

PLUGGING  
FILE SEC. 12 T. 34 R. 26w  
BOOK PAGE 104 LINE 14

THIS "A" #1

Well Record

Location: C/ W/2 Sec. 2-345-26W  
 Meade County, Kansas

Commenced: August 1, 1956  
 Completed: August 29, 1956  
 (rotary)

Operator: Graham-Michaelis Drilling Co.  
 1005 East Second Street  
 Wichita 1, Kansas

Contractor: Graham-Michaelis Drilling Co.  
 1005 East Second Street  
 Wichita 1, Kansas

Casing Record: 8-5/8" @ 1157' W/273 Sacks Cement  
 5-1/2" @ 5829' W/150 Sacks Cement

LOG

Sand & Gravel	35
Red Bed	70
Sand & Gravel	160
Red Bed & Gyp.	570
Red Bed & Anhydrite	1157
Anhydrite	1191
Red Bed & Shale	1630
Shale & Shells	2007
Shale & Lime	2396
Lime	2475
Lime & Shale	3024
Chalk	3068
Lime & Shale	3740
Lime, Chalk & Shale	3838
Lime & Shale	4557
Lime	5217
Lime & Shale	5262
Lime	5629
Shale & Lime	5672
Lime	5700
Sandy Lime	5732
Lime & Shale	5778
Lime	5830, RTD.

RECEIVED  
 STATE CORPORATION COMMISSION  
 FEB 18 1959  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

STATE OF KANSAS )  
 ) ss.  
 COUNTY OF SEDGWICK)

The undersigned, GRAHAM-MICHAELIS DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MICHAELIS DRILLING COMPANY

By John L. James  
 John L. James  
 Geologist.

Subscribed and sworn to before me  
 this 13th day of September, 1956.

Mary L. Barnes

My commission expires: 11/7/57.

PLUGGING  
 FILE SEC. 12 T. 34R 26W  
 BOOK PAGE 104 LINE 14