

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 119-20,673-0000

LEASE NAME David Wilson

WELL NUMBER #1

SPOT LOCATION NE NE NE

SEC. 10 TWP. 34 RGE. 26 (X) or (W)

COUNTY Meade

Date Well Completed 10-4-84

Plugging Commenced 12-4-84

Plugging Completed 12-7-84

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468 Tulsa, OK 74121-1468

PHONE # (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Dry  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, KS

Is ACO-1 filed? Yes If not, is well log attached? --

Producing formation None Depth to top -- bottom -- T.D. 6200

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Atoka</u>	<u>Dry</u>	<u>5676</u>	<u>5715</u>	<u>8-5/8"</u>	<u>850'</u>	<u>-0-</u>
<u>Morrow</u>	<u>Dry</u>	<u>5715</u>	<u>5776</u>	<u>5-1/2"</u>	<u>6202'</u>	<u>4200'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pumped 2 sxs hulls + 20 sxs cmt. Displaced w/110 bbls mud. Plug spotted 4910-4760. Pressure to 1000#. Held okay. Pumped 40 sxs cmt 1400' to 1300' & displaced w/mud to 900'. Pumped 40 sxs cmt. 900' to 800' & displaced w/mud to 400'. Pumped 20 sxs cmt 400' to 350' & displaced w/mud to 40'. Put bridge & 10 sxs cmt 40' to 4' - cut off 8-5/8", 3-1/2' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497  
Address Box F, Sublette, KS 67877

STATE OF Oklahoma COUNTY OF Tulsa, ss.

T.T. Jacobson (employee of operator or  
(XXXXXX) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) T.T. Jacobson

(Address) P. O. Box 21468 Tulsa, Ok 74121-1468

SUBSCRIBED AND SWORN TO before me this 9th day of Jan., 1985

Jonna M. Krapp  
Notary Public

My Commission expires: Nov. 22, 1986

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 11 1985  
CONSERVATION DIVISION  
Wichita, Kansas