


15-119-10316-0000
9

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



MEADE County. Sec. 9 Twp. 34 Rge. 26W (E) (W)
 Location as "NE/CNW/SW" or footage from lines. C NW
 Lease Owner SANTA FE PIPE & SUPPLY
 Lease Name ROGERS-PAINTER UNIT Well No. 1
 Office Address P. O. BOX 562 - GREAT BEND, KANSAS
 Character of Well (completed as Oil, Gas or Dry Hole) GAS
 Date well completed MAY 17 19 57
 Application for plugging filed NOVEMBER 21 19 61
 Application for plugging approved NOVEMBER 22 19 61
 Plugging commenced DECEMBER 1 19 61
 Plugging completed DECEMBER 7 19 61
 Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Mr. W.L. Lackamp
 Producing formation Depth to top Bottom Total Depth of Well 6011 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1245'	NONE
				5 1/2	6007'	2680'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

5863' - 5800' SAND
 5800' - 5770' 5 SACKS CEMENT
 5770' - 600' MUD
 600' - 590' ROCK BRIDGE
 590' - 530' 20 SACKS CEMENT
 530' - 40' MUD
 40' - BASE 10 SACKS CEMENT

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor GLENN & SMITH PIPE PULLING COMPANY
 Address P. O. BOX 114 - ELLINWOOD, KANSAS

STATE OF _____, COUNTY OF _____, ss.
 _____ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
 (Signature) *[Signature]*
 P. O. BOX 562 - GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of January, 1962
[Signature]
 My commission expires April 1, 1963

RECEIVED
 STATE CORPORATION COMMISSION

JAN 19 1962
 1-19-62
 CONSERVATION DIVISION
 Wichita, Kansas

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-119-10316-0000

Company: TENNESSEE GAS TRANSMISSION CO.
Farm: Roger Painter Unit No. 1

SEC. 9 T. 34 R. 26W
C. NW



Total Depth. 6011
Comm. 4-1-57 Comp. 5-17-57
Shot or Treated.
Contractor. Jones, Shelburne & Farmer, Inc.
Issued. 8-3-57

County Meade

KANSAS



Elevation. 2286 DF

Production. 3,000,000 CFHPD

CASING:

8 5/8 @ 1245' w/ 500 sx cmt.
5 1/2 @ 6007' w/ 200 sx cmt.

Figures indicate Bottom of Formations.

surface	200
shale & red bed	1241
anhydrite	1246
shale, red bed & sand	1420
shale & shells	1985
shale & lime	2520
lime & shale streaks	2580
lime & shale	2885
lime & shale streaks	2935
shale & lime	3970
shale & shells	4085
shale	4160
shale & lime	4265
shale	4445
lime & shale	4760
lime	4810
lime & shale	4895
lime	4950
lime & shale	4995
lime	5065
lime & shale	5105
lime	5155
lime & shale	5275
lime	5307
lime & shale	5450
lime	5950
lime & shale	6011
Total Depth	

TOPS:

Morrow	5788
Morrow sand	5817
Mississippi	5833

RECEIVED
STATE CORPORATION COMMISSION

JAN 19 1962

CONSERVATION DIVISION
Wichita, Kansas