

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 119-20703-0000

LEASE NAME Wanda Smith

WELL NUMBER 1-36

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 36 TWP. 34S RGE. 27W (E) or (W)


COUNTY Meade

Date Well Completed 5-13-85

Plugging Commenced 5-25-93

Plugging Completed 5-28-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
Office within 30 days.



LEASE OPERATOR Zinke & Trumbo Ltd.

ADDRESS 1202 E. 33rd Suite 100 Tulsa, Okla. 74105

PHONE# (918) 743-5096 OPERATORS LICENSE NO. 8060

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Glenn Barlow

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Chester Depth to Top 6034 Bottom 6060 T.D. 6300

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1525	0
				4 1/2	6297	2835

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 20 sks. of cement & 1 sk. of hulls to 5900

Pump 50 sks. of cement from 1560 to 1460

Pump 40 sks. of cement from 500 to 400

Put 10 sks. of cement from 40 to 0 Cut off & cap 8 5/8 4' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Seward, ss.

David Rice, agent (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David Rice

(Address) Crown Consulting, Inc., P. O. Box 1816 Liberal, KS 67905-1816

SUBSCRIBED AND SWORN TO before me this 17th day of June 1993

Hele M
Notary Public JUN 18 1993

My Commission Expires: _____



CONSERVATION DIVISION
Wichita, Kansas Form CP-4
Revised 08-84