

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 67202
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-119-21014-0000

LEASE NAME Lee "36"

WELL NUMBER 1A

660 Ft. from S Section Line

2410 Ft. from E Section Line

SEC. 36 TWP. 34S RGE. 26 (E) or (W)

COUNTY Meade

Date Well Completed 1/8/00

Plugging Commenced 4/20/00

Plugging Completed 4/21/00

6-19-00
 JUN 19 2000

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

CONSERVATION DIVISION
 WICHITA, KS

LEASE OPERATOR Mewbourne Oil Company

ADDRESS P. O. Box 7698, Tyler, TX 75711

PHONE (903) 561-2900 OPERATORS LICENSE NO. 32459

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 14, 2000 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Submitted with ACO-1.

Producing Formation Chester Depth to Top 5994' Bottom 6017' T.D. 6500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Cherokee		5732'	5859'	20"	60'	0'
Morrow Shale		5859'	5909'	13 3/8"	219'	0'
Chester SS		5909'	5967'	8 5/8"	827'	0'
Chester LS	Gas	5967'	6348'	4 1/2"	6500'	4756'
Basal Chester SS		6348'	6500'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

4/20/00: Displace hole w/100 bbl mud. Pump from surface. Set CIBP @ 5875' w/ 2sx cmt on top.

4/21/00: Cut 4 1/2" casing off @ 4756'. Pull casing to 840', pump 50 sx cmt from 840' to 700'. Displaced w/12 bbl mud. Pull casing up to 360'. Pump 40 sx cmt from 360' to 260'. Displaced 5 bbl mud. Pull casing to 40', circulated 10 sx cmt to surface. Cut off & weld steel I.D. plate 4' BGL.

Name of Plugging Contractor Jerry Dunkin Well Services, Inc. License No. 8733

Address P.O. Box 389, Enid, OK 73702

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mewbourne Oil Company

STATE OF Texas COUNTY OF Smith, ss.

Janet Burns (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 7698, Tyler, TX 75711

SUBSCRIBED AND SWORN TO before me this 16th day of June, 2000

My Commission Expires: CHERYL LITTLE
 Notary Public
 STATE OF TEXAS
 My Comm. Exp. 5-30-2002



[Signature]
 Notary Public

