


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Meade County. Sec. 35 Twp. 34S Rge. (E) 26(W)

Location as "NE/CNW4SW4" or footage from lines SW/4 SW/4 NE/4
Lease Owner Graham-Michaelis Drilling, Inc.
Lease Name Florence Walker Well No. 1
Office Address 211 North Broadway, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed June 1957
Application for plugging filed by service company 1968
Application for plugging approved 1968
Plugging commenced August 31, 1968
Plugging completed September 3, 1968
Reason for abandonment of well or producing formation Non-commercial

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production August 1968
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves, agent for Meade County
Producing formation Morrow Sand Depth to top 5907 Bottom 5928 Total Depth of Well 6111 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1228.26'	none
				5 1/2"	6110.	2832.89'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped in 25 sacks cement to plug perforations at 5907'. Plug at 5400'. Cement plug with 35 sacks cement 700' to 600'. Filled hole with mud to 45'. Cement plug with 15 sacks cement at 45' to 0'.

RECEIVED
STATE CORPORATION COMMISSION
OCT 25 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sargents Casing Pulling Service
Address Box 506, Liberal, Kansas 67901

STATE OF Kansas, COUNTY OF Sedgwick, ss.


Jack L. Yinger (employee of owner or contractor or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Yinger
Jack L. Yinger - Geologist
211 North Broadway, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of October, 1968

My commission expires July 25, 1972

Muriel F. C. Jeram
Muriel F. C. Jeram
Notary Public.



FORMATION

FROM TO

Clay & sand	0	40
Red bed & lime	40	970
Shale, lime, anhydrite	970	1276
Lime & shaly lime	1276	1402
Shale	1402	1715
Lime & shale	1715	1880
Lime	1880	2508
Shale & lime	2508	2828
Lime, strks shale	2828	3957
Shale	3957	4240
Lime & shale	4240	4275
Limy shale	4275	4457
Lime & shale	4457	4542
Shale	4542	4590
Lime	4590	4635
Shale	4635	4662
Lime	4662	5858
Shale	5858	5888
Lime	5888	5895
Shale	5895	5907
Sand & lime	5907	5938
Shale & lime	5938	5955
Lime	5955	6111
		T.D.

Drilling Commenced 5-21-57
 Drilling Completed 6-15-57

CASING RECORD:

8-5/8" at 1228.26' cemented to surface with 1000 sacks.

5 1/2" at 6110' w/200 sacks cement.
Top cement 5700'

Coring Record:

No. 1: 5901-5940' rec. 39': 6 1/2' shale; 3 1/2' lime; 3' sand; 3' shaly lime; 2' sand; 2 1/2' lime; 4' sand; 2 1/2' sdy. lime; 1' sand; 7 1/2' shale; 2 1/2' shaly lime; 1' sand, no show.

Drill Stem Tests

#1: 5962-6041' open 1 hr. gas 11 min., 33 MCFD. FP 95-110#, BHP 1570#. Rec. 270' gas cut mud.

#2: 6050-6111' open 3/4 hr. weak blow 22 min. and died. Rec. 10' mud. FP 20-50#; BHP 85#.

Geological Tops:

Heebner Shale	4493'
Lansing Lime	4662'
Marmaton Lime	5361'
Morrow Shale	5858'
Morrow Sand	5907'
Chester Lime	5955'

I hereby certify that the foregoing is a true and correct copy of the F. Walker No. 1 well log as recorded on the books of Sun Oil Company, Tulsa, Oklahoma.

J. H. Allen

 J. H. Allen

STATE OF OKLAHOMA)
) SS
 COUNTY OF TULSA)

Subscribed and sworn to before me this 10 day of July, 1958.

Blanche Faith

 Notary Public

My Commission Expires:

5-9-59

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 3 1968
 CONSERVATION DIVISION
 Wichita, Kansas