

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 South Market Room 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R. 82-3-117

API NUMBER 15-119-20651-0000

LEASE NAME Mary Taylor

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 60 days.

WELL NUMBER 33  
660 Ft. from N/S Section Line

1320 Ft. from E/W Section Line

LEASE OPERATOR Herman Loeb

SEC. 33 TWP. 34s RGE. 26 XXXXX (W)

ADDRESS P.O. Box 524, Lawrenceville, IL 62439

COUNTY Meade

PHONE# 812 853-3813 OPERATORS LICENSE NO. 3273

Date Well Completed \_\_\_\_\_

Character of Well Good

Plugging Commenced 7/25/00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7/31/00

The plugging proposal was approved on 7/25/00 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? no

Producing Formation Marmington Morrow sand, Cherokee Depth to Top 5481 Bottom 5968 T.D. 6000 CIBP

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1524	None
				5 1/2	6319	2400

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Lay down rods and tubing, set CIBP at 5412, dump 2sx cement with dump bailor, stretch and cut casing at 2400, lay down casing, Allied pump 300 hulls, 10sx jel, 50sx cement, 10 jel, 100 hulls, 8 5/8 wiper plug, 150sx cement, 60/40, 6% jel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, 107 W. Fowler, Medicine Lodge, KS 67104


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Herman Loeb

STATE OF Kansas COUNTY OF Barber, ss.

Alan Vratil (Employee of Operator) or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Alan Vratil

(Address) Medicine Lodge, KS 67104



SUBSCRIBED AND SWORN TO before me this 8 day of July, 2000

Glenda Morrison  
Notary Public

My Commission Expires: 11/30/02

RECEIVED  
STATE CORPORATION COMMISSION

AUG 10 2000

Form CP-4

CONSERVED  
Wichita, Kansas