

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Coltrane Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 119-20665-0000

LEASE NAME Finchman

WELL NUMBER 3-31

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2310 Ft. from X^N Section Line

2310 Ft. from X^W Section Line

SEC. 31 TWP. 34S RGE. 26W (E) or (W)

COUNTY Meade

LEASE OPERATOR Zinke & Trumbo, Ltd.

ADDRESS 1202 E. 33rd Suite 100 Tulsa, Oklahoma 74105

PHONE (918) 743-5096 OPERATORS LICENSE NO. 8060

Date Well Completed 11-02-84

Character of Well Gas

Plugging Commenced 2-9-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-19-93

The plugging proposal was approved on 2-9-93 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Morrow & Chester Depth to Top 6031 Bottom 5918 T.D. 6300

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|------|-------|--------|------------|
| Morrow | gas | 5918 | 5934 | 8 5/8 | 1479 | 0 |
| Chester | gas | 6000 | 6031 | 4 1/2 | 6297 | 3018. |
| | | | | | | |

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
Pump 20 sks. of cement & 2 sks. of hulls to 5800

Pump 50 sks. of cement from 1520 to 1420

Pump 40 sks. of cement from 600 to 500

Put 10 sks. of cement from 40 to 0 Cut off & cap 8 5/8 4' below ground level
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O.Box 506 Liberal, Kansas 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Zinke & Trumbo, Ltd

STATE OF Kansas COUNTY OF Seward, ss.

Keith Hill (Employee of Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 1816, Liberal, KS 67905-1816

SUBSCRIBED AND SWORN TO before me this 17th day of March, 19 93

NOTARY PUBLIC, State of Kansas
Seward County
Comm. Expires: HELEN M. SMITH
My Appt. Exp. 3-5-92

[Signature]
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
MAR 18 1993
CONSERVATION DIVISION
Wichita, Kansas