

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Neas of Allen & Parker has this

date requested permission to plug the following described well:

Mr. Neas guarantees payment of the plugging fee.

Operator's full Name: Allen & Parker

Complete Address: Box 906, Perryton, Texas

Lease Name: Adams Well No. 1

Location: C NW NE Sec. 20 Twp. 34 Rge. 30 XX (E) (W)

County: Meade Total Depth 6000' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Neas was instructed to plug the well as follows:

8 5/8" to 1493' circulated w/ cement. 3 1/2" to 6000' cemented.


Top perforations 5912' Plug bottom w/ 15 sacks cement.

Top of cement 5796' Mud 5796' to 1387'

Spotted 35 sacks cement 1387' to 1287' Mud 1287' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent