

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY	Governor
WILLIAM L. MITCHELL	Chairman
JAMES O. GREENLEAF	Commissioner
HARRY G. WILES	Commissioner
RAYMOND B. HARVEY	Secretary
E. EDWARD JOHNSON	Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 - 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Phillips of Graham-Michaelis has this

date requested permission to plug the following described well:

Mr. Phillips guarantees payment of the plugging fee.

Operator's full Name: Graham-Michaelis Drlg., Inc.

Complete Address: 211N. Broadway, Wichita, Kansas

Lease Name: Wright Well No. 1-18

Location: C NE NE Sec. 18 Twp. 34 Rge. 30 (E) (W)

County Meade Total Depth 6422' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Phillips was instructed to plug the well as follows:

8 5/8" to 1547' circulated w/ cement. Mud 6422' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Weld Plate on 8 5/8" .

Very truly yours,

Edgar J. Lewis
Conservation Division Agent