



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Shenandoah has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Shenandoah Oil Corporation

Complete Address: Box 1387, Liberal, Kansas

Lease Name: Eugene Keabing Well No. 1

Location: C NE SW Sec. 14 Twp. 34 Rge. 31 ~~(E)~~ (W)

County: Seward Total Depth 6150' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

- 16" to 71' circulated w/ cement. 8 5/8" to 1415' circulated w/ cement.
- 4 1/2" to 5686' cemented. Top perforations 5342'
- Plug bottom w/ 20 sacks cement Top of cement 5000'
- Mud 5000' to 900' Spot 35 sacks cement 900' to 800'
- Mud 800' to 45' Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent