



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Burris of Leben et al has this

date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Leben et al

Complete Address: 200 W. Douglas, Wichita, Kansas

Lease Name: H.N.B. & T Well No. 1

Location: C NE SE Sec. 17 Twp. 34 Rge. 31 (E) (W)

County: Seward Total Depth 6135' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Burris was instructed to plug the well as follows:

8 5/8" to 1450' circulated w/ cement. Mud 6135' to 1100'

Spot 35 sacks cement 1100' to 1000' Mud 1000' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent